8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantities of work.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork	C. yd.	4,126
Cutting grips	„	1,475
Turfing	S. yd.	2,807
Gravel backing in rear of revetment	C. yd.	733
New stone work	„	1,990
Old stone work	„	434
Preparing and fixing new grade stones with bottom slabs	No.	32
Vis-á-vis stones with bottom slabs	„	32
B. M. stones with bottom slabs	„	2
Register number stone	„	1
Gauge stones	„	2
Breaching the bund, letting out water to facilitate work and refilling the same	C. yd.	768
Proposed new sluice—		
Earthwork, excavating and refilling including consolidation	C. yd.	345
Concrete in surki mortar	C.ft.	355
Brick in surki mortar	„	283
Archwork in do	„	22
Stone slabs, 3″ thick	S. ft.	49
Do 6″ „ dressed	„	70
Preparing holes for upper and lower orifice slabs	Lump sum.	
Fixing gibbets	Lump sum.	
Plastering with surki mortar	Sqr.	2·00
E. I. pipes of 9″ diameter including carting and fixing	R. ft.	54
Baling water	Lump sum.	
Plug and rod	Do	
Left waste weir—		
Earthwork, excavation	C. yd.	221
Blasting rock	„	6
Brick in surki mortar	C. ft.	1,189
Burnt stone slabs, 4 to 6 inches thick, dressed	S. ft.	406
Plastering with surki mortar	Sqr.	2·62
Rough stone work, new	C. yd.	103
Do old, with new jelly	„	22
Clearing draft	„	255

V. AIYASWAMI IYER,
Executive Engineer.

WATER-SUPPLY AND STORES DIVISION.

Abstract Notification dated 19th October 1911.

The attention of the public is invited to the notification dated 12th October 1911, calling for tenders for the supply of fuel to the Pumping Station, Bethamangala, published in page 1207, Part II of the *Mysore Gazette*.

The specification for jungle fuel omitted in last notification is herein published for information.

Specification.

The wood to be jungle fuel.

The maximum and minimum dimensions which will be accepted are given below:—

Length.		*Thickness.*	
Maximum.	Minimum.	Maximum.	Minimum.
24″	18″	7″	3″

The billets are to be sawn and not chopped. Billets of over 7 inches in diameter to be split.

The wood to be stacked by the contractor in the portion approved of by the Executive Engineer or his representative.

Stacks must be of rectangular shape. The sides being vertical and straight and the top level. The wood must be laid evenly straight and close, the pieces composing the walls must be laid at right angles to the direction of such walls, having first been sawn to an uniform length as above.

The interior of the stacks must be packed as closely as possible, the pieces being regularly laid with their lengths all in the one direction, which leave no vacant space.

The stacks to be built of such dimensions that the cubical contents of each is a multiple of 75 cubic feet.

$15' \times 10' \times 5' = 750$ cubic feet $= 10$ tons.

Seventy-five cubic feet of closely packed wood will be accepted as equivalent to a ton.

The Executive Engineer or his representatives will inspect the wood as it is being stacked and shall have power to reject any pieces that are hollow, rotten or otherwise unsuitable for fuel for boilers; he will also satisfy himself that the pieces are in accordance with the dimensions specified above, and that the stacks are built as required. He shall have power to reject any stacks that do not, in all respects, comply with the terms of the specification.

The wood must be at the risk of the contractor until it is stacked, measured and accepted by the Executive Engineer or his representatives.

When stacks are taken over, the contractor or his representative must be present during the measurement and must sign the record of measurement in token of his agreement to the correctness thereof.

Soft wood unsuitable for steaming purposes will not be accepted.

Jali, thopyala, devadari, hunse, chigari, heddarne, gorve and other equally hard wood than those specified above and which the contractor would like to supply, may be supplied after he has got the previous sanction of the Executive Engineer or his representatives. A cart-load of the proposed fuel to be brought in first when the same will be tested and if suitable the contractor will be given permission in writing to such wood also in addition to the list of wood already approved of.

K. SRINIVASA IYENGAR,
Executive Engineer.

Notice———dated October 1911.

Tenders will be received by the undersigned up to 12 noon on Saturday the 4th November 1911, for supply of clothing for the Mysore Imperial Service Transport Corps for the year 1911-12.

Rates should be given separately for (1) making up clothing with cloth, etc., supplied from this office and (2) for supplying material and making up clothing.

Sealed samples can be seen and any further particulars required obtained at this office.

R. G. JONES, LT.-COL., I.A.,
Military Secretary
to His Highness the Maharaja of Mysore.

PRIVATE ADVERTISEMENTS.

BEFORE THE HON'BLE THE RESIDENT IN MYSORE AT BANGALORE.

Application in file No. 257 *of* 1911.

In the matter of the estate of A. Srinivasa Rao, late of Bangalore City,
but now ... ... *Deceased.*
Padmavathiboyi ... ... *Applicant.*

Whereas Padmavathiboyi, resident of Siddikatte, Bangalore City, claiming to be the widow of the said A. Srinivasa Rao, deceased, has applied for a certificate under Section 17, Act VII of 1889, to collect the sum of Rs. 2,000 due to the estate of the said deceased, under a Policy of Insurance No. 18985 with the Empire of India Life Assurance Company (Ltd.), Bombay:

Notice is hereby given of the said application; and all claimants in the estate of the said A. Srinivasa Rao, deceased, are invited to appear before the Hon'ble the Resident at Bangalore, on Saturday the 4th of November 1911 at 11 A.M., when the petition of the said Padmavathiboyi will be heard, and the right to the certificate determined.

Given under my hand and seal, this 26th day of September 1911.

By Order,
N. S. TIRUMALAIENGAR,
Registrar.

VACANCY.

MYSORE CITY MUNICIPALITY.

Dated the 17*th October* 1911.

WANTED.

Applications are invited for the posts of temporary Surveyors on a salary of Rs. 25 per month. The applicants must have passed the Sub-Overseer's test from the Mysore Engineering School or any other recognized Engineering School. They must agree to serve the Municipal Council for a period of nine months. Applications with testimonials should reach the undersigned before the 5th of November 1911.

M. G. KRISHNASAMI RAO,